

4. AIRCRAFT CHECKLIST CESSNA 208

SCHUMAN AVIATION COMPANY, LTD. CESSNA 208B NORMAL CHECKLIST		
1.	Exterior Pre-Flight _____	Complete
2.	Weight & Balance _____	Complete
3.	Passenger Briefing (if necessary) _____	Complete
4.	Battery Cable _____	Connected
BEFORE ENGINE START		
1.	Cabin doors & Windows _____	Secured
2.	Control Lock _____	Removed
3.	Seat Belts, Shoulder Harnesses _____	Secured
4.	Standby Flap Switches _____	Closed
5.	Cabin Heat Firewall Shutoff _____	In
6.	Fuel Shutoff _____	In
7.	Cabin Heat Mixing Air _____	In
8.	Bleed Air Heat _____	Off
9.	Condition _____	Cutoff
10.	Power _____	Idle
11.	Emergency Power _____	Normal
12.	Air Conditioner _____	Off
13.	Parking Brake _____	Set
14.	Alt. Static Air Source _____	Closed
15.	Ignition _____	Norm
STARTING ENGINE		
1.	Battery _____	On
2.	Lights _____	As Req'd
3.	Volt/Ammeter (Volts) _____	24V min
4.	Engine Instruments _____	Checked
5.	Boost Pump _____	On
6.	Starter _____	Start
7.	Ng _____	Stabilized 12% min
8.	Condition _____	Low Idle
9.	Starter Ng 52% Minimum) _____	Off
10.	Boost Pump _____	Norm
11.	Standby Power _____	On
12.	Avionics _____	On
13.	Engine Instruments _____	In the Green
STARTING ENGINE (EPU)		
1.	External Power Switch _____	Off
2.	Battery _____	On
3.	Volt/Ammeter (Volts) _____	20V in
4.	Battery _____	Off
5.	EPU Cable _____	Connect
6.	External Power Switch _____	BUS
7.	Volt/Ammeter (Volts) _____	24V min
8.	External Power Switch _____	START
9.	Battery _____	On
10.	Lights _____	As Req'd
11.	Engine Instruments _____	Checked
12.	Boost Pump _____	On
13.	Starter _____	Start
14.	Ng _____	Stabilized 12% min
15.	Condition _____	Low Idle
16.	Starter (Ng 52% Minimum) _____	Off
17.	Boost Pump _____	Norm
18.	External Power Switch _____	Off
19.	GPU Cable _____	Disconnect
20.	Avionics _____	On
21.	Engine Instruments _____	In the Green