



March 23, 2015

Proposal # [REDACTED]

Andy Colloton



Phone:
Cell:
E-mail:



Reference: Spirit of Boston Cruise Ship
Fairhaven Shipyard & Marina
50 Fort Street
Fairhaven, MA 02719
4 3 Bars & 2 Wait Stations



We propose to supply all supervision, labor, materials and equipment necessary to perform the following scope of work: 3 Bars & 2 Wait Stations – approx. 960 square feet of floor (integral cove base excluded from scope of work). Measurements provided by Andy C. from Cooley Marine Management

**INSTALLATION OF BASF MASTERTOP 1843 SRS CQ (QUARTZ) FLEXIBLE MMA/ACRYLIC FLOORING SYSTEM
(CURES 1 HOUR AFTER INSTALLATION – 2-3 DAY PROJECT)**

- Step 1: Surface preparation to be performed by Cooley Marine Management – mechanically beadblast, sand or grind all steel surfaces down to white, ferrous metal to provide an anchor profile into the surface.
- Step 2: IFS to use wire brushes to skim pre-prepared surfaces should metal have oxidized before IFS arrival.
- Step 3: Apply a full coat of PPG Amerlock 2 Epoxy Primer.
- Step 4: Apply a full prime coat of MasterTop SRS 51P Primer/Sealer.
- Step 5: Apply a base coat of MasterTop SRS 40TCSL (Flexible).
- Step 6: While 40TCSL base coat is still wet, a full broadcast of 'S' Grade colorquartz will be introduced.
- Step 7: Apply two (2) full finish coats of MasterTop SRS 71TC Clear Satin Topcoat.



ALL PRICES ARE EFFECTIVE UNTIL DECEMBER 31, 2015

Qualifications:


- 1) Pricing based on:
 - a. Floor substrate – Existing metal/steel decking (to be prepped prior to IFS arrival)
 - b. **Wall substrate – n/a (no integral cove base to be installed)**
 - c. Shifts – Normal, Day (Monday – Friday)
 - d. **Phases/mobilizations – One**
 - e. Sloping – Not factored into proposal
 - f. **Misc. Project Details –**
 - i. Existing metal decking to be prepped prior to IFS start up
 - ii. Integral cove base not included in scope of work/pricing above
- 2) This is a hand applied & broadcasted resinous flooring system, therefore imperfections may be seen. This does not affect the functionality of the system.
- 3) ADDENDUMS/RFIs – None
- 4) Moisture tests not necessary for this project
- 5) Any new concrete (Portland based) must cure for 28 days before resinous flooring installation.
- 6) Any major concrete patching/repairs will be performed on a time & material basis & included in final invoice.
- 7) Any downtime caused to our laborers while working around other trades will be back charged directly to GC/owner



Reference: Spirit of Boston Cruise Ship
Fairhaven Shipyard & Marina
50 Fort Street
Fairhaven, MA 02719
3 Bars & 2 Wait Stations

- 8) All proposals bid from verbal measurements/blueprints/plans are subject to change based on site visit and determination of field conditions.
- 9) Electricity, water, ventilation and storage to be provided by others. Electrician to be provided at start up of project.
- 10) These products have a distinct odor during installation, which is well below OSHA limits. This odor quickly dissipates when curing process is complete. IFS will make every effort to exhaust resin odors to outside air and will not be held responsible for odor complaints.
- 11) A change order will be issued if unforeseen circumstances cause the need for additional labor or materials to complete the project properly, such as hidden deterioration, cleaning, moving of heavy equipment, extensive crack repair, fill penetrations, etc.
- 12) Warranty to be 1 year from date of installation.
- 13) Payment terms: 50% Deposit; Balance due upon completion/receipt of invoice.

INNOVATIVE FLOOR SYSTEMS, INC.


Cathy Mavris
President

Signature of 

Date

4/10/15

Print Name

ANDREW MCNAB

Title

OPERATIONS.