

Attachment
2



Shipyard, Inc.
[Redacted]
Phone: [Redacted] Fax: [Redacted]

Wednesday, February 19, 2020

Marlin Oilfield Divers
Attn: Logan Moore

[Redacted]

Re: M/V Joseph Bisso

Dear Mr. Logan,

Allied Shipyard, Inc. is pleased to submit to you the following bid prices for repairs as detailed below.

1: Provide labor, material and equipment to set blocks, haul the vessel up on dock and hold for repairs. When repairs are complete, launch vessel.

Bid Price-----\$ [Redacted]

2: Provide labor, material and equipment to connect shore power to the vessel during repair. When repairs are complete, disconnect as original.

Bid Price-----\$ [Redacted] per connect
\$ [Redacted] per disconnect
\$ [Redacted] per day usage

3: Provide labor, material and equipment to remove the port and starboard propellers for repairs. When repairs are complete, reinstall propellers as original.

Bid Price-----\$ [Redacted] per

4: Provide labor, material and equipment to remove the port and starboard shafts for repairs. When repairs are complete, reinstall as original.

Bid Price-----\$ [Redacted] per

5: Provide labor, material and equipment to disconnect the steering gear and remove the port and starboard rudders for repairs. When repairs are complete, reinstall all as original.

Bid Price-----\$ [Redacted] per

6: Provide labor, material and equipment to open and clean valves for inspection. When the inspection is complete, reinstall valves as original.

Bid Price-----\$ [REDACTED] per inch

7: Provide labor, material and equipment to remove and reinstall anodes. Touch up the paint after installation.

**Bid Price-----\$ [REDACTED] per owner furnished
\$ [REDACTED] per shipyard furnished**

8: Provide a marine chemist for hot work.

Bid Price-----\$ [REDACTED] per visit

9: Provide competent person to check tanks and post readings.

Bid Price-----\$ [REDACTED] per day

10: Provide labor, material and equipment to wrap the cabin, hang tarps and set up blasting equipment. Blast the vessel from the keel to the cap rail, inside the bulwarks aft of all deck equipment and deck perimeter around the boards aft of all deck equipment. Remove sand and blow down to prep for paint. Apply (2) coats of primer and (2) coats of antifouling from the keel to the waterline. Apply (1) coat of zinc, (1) coat of primer and (1) top coat from the waterline to the cap rail, inside the bulwarks and the deck perimeter. Cut in the waterline and paint hull markings. (Owner furnished coatings)

Bid Price-----\$ [REDACTED]

Thank you for allowing Allied Shipyard the opportunity to bid on your job. We look forward to working with you on this project. If you have any questions or require any additional information, please do not hesitate to contact us at [REDACTED]

Sincerely,
Scotty Martin
Operations Manager